

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20979-00-00
Spot: E2NENW Sec/Twnshp/Rge: 18-15S-13W
4620 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KRUG Well #: 1
County: RUSSELL Total Vertical Depth: 3360 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3286		
PROD	4.5	3360		125 SX
SURF	8.625	347		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2013 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM CO Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 500 # hulls.
Packer stuck in well at 2870'.
CIBP set over Arbuckle perforations.
Will plug well from 2870'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 830' and 325'.
Ran tubing to 2850' and pumped 100 sx cement.
Pulled tubing to 1350' and pumped 45 sx cement w/100 # hulls.
Pulled tubing to 830' and pumped 45 sx cement w/100 # hulls.
Pulled tubing to 325'. Circulated cement to surface with 25 sx cement and 100 # hulls on casing and surface pipe.
Pulled tubing. Tied to casing and topped off with 2 sx cement pressured to 350 psi.

Perfs:

Top	Bot	Thru	Comments
3060	2993		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

KCC WICHITA
JUN 19 2013
RECEIVED

District: 04

Signed Bruce Rodie
6/6/13
(TECHNICIAN)

CM

JUN 06 2013