

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20233-00-00  
Spot: W2SESESW Sec/Twnshp/Rge: 33-8S-24W  
330 feet from S Section Line, 2155 feet from W Section Line  
Lease Name: HOLLEY LKC UNIT Well #: 211  
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4039		675 SX
SURF	8.625	328		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/04/2013 1:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOE SMITH Company: EXPRESS WELL SERVICE & SUPPL Phone: (620) 275-2963

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/500 # hulls and 7 sx gel.  
Perforations at 3938' - 3943'.  
Shot perforations at 2150' and 1350'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/04/2013 8:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3900' and pumped 7 sx gel followed by 50 sx cement w/100 # hulls.  
Pulled tubing to 2550' and pumped 240 sx cement. Good circulation of cement.  
Tied on to back side. Squeezed with no cement. Hole standing full. Shut in pressure 300 psi.  
Topped off casing with 40 sx cement.

GPS: 39.30670 -100.00677

Perfs:

Top	Bot	Thru	Comments
3938	3943		

Remarks: SWIFT CEMENT TICKET # 24329

Plugged through: TBG


KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed

  
6/28/13 (TECHNICIAN)

CM

Form CP-2/3

JUN 07 2013