

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19064-00-00  
Spot: SESESE Sec/Twnshp/Rge: 12-17S-11W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: KRAUTWURST Well #: 2  
County: BARTON Total Vertical Depth: 3316 feet

Operator License No.: 4058

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3314		
SURF	10.75	190		

Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/13/2013 10:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Recd. from: KEVIN WILES

Company: AMERICAN WARRIOR

Phone: (620) 275-9231

Proposed Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls and 20 sx gel.  
Plugging  
Method:

Plugging Proposal Received By: BRUCE BASYE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/12/2013 3:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1300', 650' and 175'.  
Ran tubing to 3140' and pumped 20 sx gel followed by 100 sx cement w/100 # hulls.  
Pulled tubing to 1350' and pumped 140 sx cement w/200 # hulls.  
Pulled tubing to 650'. Circulated cement to surface with 210 sx cement.  
Pulled tubing and topped off with 40 sx cement.  
06/14/13- checked to see if cement had dropped. Cement within 15' of surface.

GPS: 38.3858069 -09.48121

KCC WICHITA

Remarks: ALLIED CEMENT COMPANY TICKET # 60441

**JUN 19 2013**

Plugged through: TBG

**RECEIVED**

District: 04

Signed

*Bruce Rode*  
6/19/13  
(TECHNICIAN)

CM

**JUN 17 2013**

Form CP-2/3