

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26515-00-00  
Spot: N2N2SE Sec/Twnshp/Rge: 15-12S-17W  
2310 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: SCHMEIDLER ET AL Well #: 2-15  
County: ELLIS Total Vertical Depth: 3760 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1031		400 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2013 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 06/08/2013 6:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3640 w/50 sx  
2nd plug @1375 w/25 sx  
3rd plug @1075 w/40 sx  
4th plug @800 w/80 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY OIL

Plugged through: DP

KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed *Case Morris*  
6/20/13 (TECHNICIAN)

JUN 12 2013