

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21614-01-00  
Spot: N2N2NWNW Sec/Twnshp/Rge: 6-32S-19W  
165 feet from N Section Line, 660 feet from W Section Line  
Lease Name: BRENTLEY Well #: 1-6H  
County: COMANCHE Total Vertical Depth: 6435 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3275		
CIBP		5300		WITH 5 SX CMT
COND	20	90		12 sx cement
	11 7	5618		185 sx cement
	L1 43.5	9710		450 sx ce,emt
SURF	9.625	1009		435 SX

\* DIFFER. FOR  
HORIZONTAL  
LEG ONLY.  
*[Signature]*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2013 8:00 AM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: WANDA LEDBETTER Company: SANDRIDGE EXPLORATION Phone: (405) 429-6536

Proposed Plugging Method: TOC @ 3550' | CIBP set @ 5300' | 5 sks class H cement dumped on top of CIBP @ 5300' | Perfs @ 3250' and squeezed w/500 sks class H cement | Perfs @ 3150' | CIBP set @ 3275'

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 04/27/2013 4:12 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

**\*\*PLUGGING OFF HORIZONTAL LEG ONLY\*\*** SET CIBP @ 5300' WITH 5 SX CLASS H CMT ON TOP. PERFORATED @ 3250' & SQUEEZED WITH 500 SX CLASS H CMT. SET CIBP @ 3275' TO SET WHIPSTOCK ON & NOW WILL DRILL WELL DEEPER VERTICALLY.

Perfs:

Top	Bot	Thru	Comments
8537	8828		
8153	8444		
7779	8084		
7400	7705		
7021	7326		
6717	6947		
6262	6568		
5883	6189		
5504	5809		
5490	9255		

KCC WICHITA

JUN 06 2013

RECEIVED

Remarks: USED CLASS H CEMEBNT BY HALLIBURTON. PLUGGED OFF HORIZONTAL LEG ONLY. INVOICE FOR INTERVAL 3275' TO 9710'.

Plugged through: TBG

RECEIVED

JUN - 3 2013

KCC DODGE CITY

Signed

*[Signature]*  
6/26/13 (TECHNICIAN)

*[Signature]*