

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20221-00-00
Spot: SESE Sec/Twnshp/Rge: 2-1S-34W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: CAHOJ NE A UNIT Well #: 1-3
County: RAWLINS Total Vertical Depth: 4150 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4197		225 SX
SURF	8.625	239		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2013 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: SWIFT SERVICES Phone: (785) 798-7113

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/900 # hulls.
Tubing stuck in well bore at 3446'. Well bore perforations: 3918' - 4121'.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 06/07/2013 1:40 PM KCC Agent: TOM CULLEY

Actual Plugging Report:

Tubing stuck in hole. Top of tubing at 3446'.
Ran tubing to 3426' and pumped 75 sx cement.
Pulled tubing to 2495' and pumped 150 sx cement w/400 # hulls.
Pulled tubing to 1786' and pumped 150 sx cement w/400 # hulls.
Pulled tubing to 893' and pumped 45 sx cement w/100 # hulls.
POOH and pumped 25 sx cement down 8 5/8" casing to pressure up to 200 psi.
Pumped 5 sx cement down 5 1/2" production casing. Hole standing full.

GPS: 39.98948 -101.09488

Perfs:

Top	Bot	Thru	Comments
4113	4121		
4087	4089		
4068	4072		
4017	4019		
3996	3998		
3974	3978		
3961	3964		
3938	3944		
3918	3924		

Remarks: SWIFT SERVICES TICKET # 24288

Plugged through: TBG


KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed


6/26/13 (TECHNICIAN)

CM

JUN 14 2013