

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21233-00-00  
Spot: NESWNEW Sec/Twnshp/Rge: 8-20S-21W  
4594 feet from S Section Line, 3316 feet from E Section Line  
Lease Name: NORTH Well #: 2  
County: NESS Total Vertical Depth: 4426 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 125 N MARKET STE 1252  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4422	0	WITH 125 SX CMT
SURF	8.625	411		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2013 8:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: RUN TBG TO 440' & PUMP 10 SX GEL - 30 SX CMT W/100# HULLS. PULL TBG TO 1500' & CIRCULATE CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/21/2013 12:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 4320' & PUMPED 5 SX GEL DUE TO CEMENTERS PROBLEMS & 30 SX CMT. PULLED TBG TO 1450' & CIRCULATED CMT TO SURFACE UP THE 4 1/2" WITH 75 SX CMT. PULLED TBG PUT & TOPPED OFF HOLE WITH 5 SX CMT. PRESSURED 8 5/8" X 4 1/2" TO 500 PSIG WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4423	4425		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: TBG

KCC WICHITA  
JUN 27 2013  
RECEIVED

District: 01

Signed

Richard M. Lacey  
6/28/13 (TECHNICIAN)

RECEIVED

JUN 25 2013

KCC DODGE CITY