

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20942-00-00
Spot: SWNESENE Sec/Twnshp/Rge: 24-17S-34W
1840 feet from N Section Line, 520 feet from E Section Line
Lease Name: SLEEPING INDIAN Well #: 2
County: SCOTT Total Vertical Depth: 4865 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: 20014 283 HWY
WAKEENEY, KS 67672

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	231		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/14/2013 1:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK BIGGE Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1430' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 260' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 05/14/2013 3:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1430' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 260' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.


KCC WICHITA
JUN 05 2013
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed


(TECHNICIAN)

RECEIVED

MAY 16 2013

KCC DODGE CITY

Handwritten initials