

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-02968-00-00
Spot: SWSESE Sec/Twnshp/Rge: 17-24S-4W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: PRIDDLE ACCT 2 Well #: 4
County: RENO Total Vertical Depth: 3369 feet

Operator License No.: 31786
Op Name: OFCIW OIL COMPANY, INC.
Address: PO BOX 756
HARTINGTON, NE 68739

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	8.625	3323		50 SX
SURF	15.5	313		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 05/24/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

6/3/13-PUMPED 50 SX HOT CEMENT @ 3300' - LET SET 2+ HOURS, TAGGED AT 3144' TUBING STUCK SHOT OFF @ 3114' - RAN TUBING INTO 2800' SPOTTED 50 SX CEMENT, TAGGED AT 2700'. WIRELINE RAN INTO 650' SHOT 4 SHOTS, RAN INTO 400' SHOT 4 SHOTS. RAN TUBING TO 650' SPOTTED 50 SX CEMENT. COULD NOT TAG CEMENT, RAN BACK INTO 650' SPOTTED ANOTHER 75 SX LET STAND OVERNITE. 6/4/2013 TAGGED CEMENT AT 299' INSIDE 8 5/8" CASING, RAN TUBING IN TO 285' TOOK 90 SX CEMENT TO FILL. DUG OUT BACKSIDE, RAN ONE INCH TUBING TO 200' CIRCULATED TO SURFACE WITH 100 SX CEMENT, LET STAND FELL BACK, ADDED ANOTHER 135 SX CEMENT. 6/5/13--2' OF CEMENT IN CELLAR.

Perfs:

KCC WICHITA
JUN 17 2013
RECEIVED

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #38580-375 SX OF COMMON CEMENT USED & 175 SX OF 60/40 4% POZ MIX. PAST TEN YEAR TA.

Plugged through: CSG

District: 02

Signed

B. J. Hope
6/26/13
TECHNICIAN)