

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21302-00-00
Spot: NWNENWSE Sec/Twnshp/Rge: 17-19S-20W
2376 feet from S Section Line, 1652 feet from E Section Line
Lease Name: YOUNG R L Well #: 1
County: RUSH Total Vertical Depth: 4500 feet

Operator License No.: 34736

Op Name: TEXAS COASTAL OPERATING COMPANY

Address: 222 W. LAS COLINAS BLVD STE 150
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4496	0	WITH 175 SX CMT
SURF	8.625	615		WITH 300 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/21/2013 10:00 AM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: GARY GORDON

Company: TEXAS COASTAL OPERATING

Phone: (214) 429-3700

Proposed
Plugging
Method:

WELL IS SANDED IN TO 713'. PERFORATE 4 1/2" @ 650'. RUN TBG TO 700' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/21/2013 12:10 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

PERFORATED 4 1/2" @ 650'. RAN TBG TO 713'. PUMPED 225 SX CMT CIRCULATING CMT TO SURFACE UP THE 4 1/2" AND THE 8 5/8" X 4 1/2" ANNULUS. PULLED TBG OUT OF HOLE & TOPPED IT OFF WITH 15 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT CEMENTING.

Plugged through: TBG

KCC WICHITA

JUN 27 2013

RECEIVED

District: 01

RECEIVED

JUN 25 2013

KCC DODGE CITY

Signed

Richard M. Lacey
7/01/13

(TECHNICIAN)