

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23005-00-00  
Spot: NWNENWNW Sec/Twnshp/Rge: 13-11S-19W  
4980 feet from S Section Line, 4600 feet from E Section Line  
Lease Name: ALLISON A Well #: 2  
County: ELLIS Total Vertical Depth: 3610 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3605		150 SX
SURF	8.625	271		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2013 11:45 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement; 500 # hulls  
Perforations: 3239' - 3451'.  
Well has been squeezed.  
Milled on well for 3 days and got to 1226'. Was loosing hole.  
GPS: 39.10208 -099.38593  
4955' FSL 4559' FEL NE NW NW

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/13/2013 1:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


Express Well Service ran in hole with tubing to 1111'. Quality rigged to tubing and mixed and pumped 80 sx cement to circulate cement to surface.  
Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 25 sx cement to pressure with 800 psi and 800 psi shut in pressure.  
Rigged to 8 5/8" casing and pumped 10 sx cement to pressure with 800 psi and 750 psi shut in pressure.

Remarks: QUALITY OILWELL CEMENTING TICKET # 6928

Plugged through: TBG

District: 04

Signed

  
7/07/13  
(TECHNICIAN)

CM

JUN 14 2013