

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22709-00-01
Spot: SWSWSESW Sec/Twnshp/Rge: 6-11S-18W
321 feet from S Section Line, 3793 feet from E Section Line
Lease Name: PEAVEY Well #: 1-INP
County: ELLIS Total Vertical Depth: 3750 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3300		
PROD	5.5	3750		200 SX
SURF	8.625	265		150 SX
T1	2	3300		

Well Type: EOR UIC Docket No: E23474.6 Date/Time to Plug: 05/21/2013 10:00 AM

Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.

Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/800 # hulls.
PBTD-3701'.
DV tool at 800' w/400 sx cement.
Squeezed at 807' w/400 sx cement.
Perforations-3085'-3504'

GPS: 39.11833 -099.36449
369' FSL 3683' FEL NW SW SE SW

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2013 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Klima ran in hole with tubing to 3300'. Quality mixed and pumped 125 sx cement w/300 # hulls mixed in.
Pulled tubing to 2500'. Quality mixed and pumped 125 sx cement w/300 # hulls mixed in.
Pulled tubing to 1000'. Quality mixed and pumped 100 sx cement w/200 # hulls mixed in to circulate cement to surface.
Pulled tubing. Topped off 5 1/2" casing w/10 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 15 sx cement to pressure with 150 psi and 100 psi shut in pressure.

Remarks: QUALITY OILWELL CEMENTING TICKET # 6952

Plugged through: TBG

KCC WICHITA
MAY 28 2013
RECEIVED

District: 04

Signed

[Signature]
TECHNICIAN)
cc to UIC 6/20/13

CM

MAY 23 2013