

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20006-00-01
Spot: SWNE Sec/Twnshp/Rge: 4-34S-32W
3322 feet from S Section Line, 2021 feet from E Section Line
Lease Name: ALEXANDER B Well #: 1
County: SEWARD Total Vertical Depth: 6252 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5800		WITH 4 SX CMT
PROD	4.5	6252	2320	WITH 200 SX CMT
SURF	8.625	1558		WITH 725 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/11/2013 8:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SET CIBP @ 5810' WITH 4 SX CMT. PLUG AT 1590' WITH 20 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN

Witness Type: NONE

Date/Time Plugging Completed: 06/11/2013 11:00 AM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 5800' WITH 4 SX CMT. 1ST PLUG AT 1590' WITH 20 SX GEL & 50 SX CMT.
2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6096	6104		
5936	5998		
5863	5916		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

KCC WICHITA

JUN 20 2013

RECEIVED


District: 01

RECEIVED

JUN 13 2013

KCC DODGE CITY

Signed


6/21/13

(TECHNICIAN)