

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20300-00-01  
Spot: W2E2SWSW Sec/Twnshp/Rge: 15-33S-34W  
618 feet from S Section Line, 761 feet from W Section Line  
Lease Name: KOCH A Well #: 1  
County: SEWARD Total Vertical Depth: 6410 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5920		WITH 4 SX CMT
PROD	4.5	6065	1620	WITH 240 SX CMT
SURF	8.625	1599		WITH 800 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2013 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SET CIBP @ 5920' WITH 4 SX CMT. PLUG AT 1630' WITH 20 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/17/2013 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5920' WITH 4 SX CMT. 6/14/13: 1ST PLUG AT 1610' WITH 20 SX GEL, 50 SX CMT. NO RETURNS. 2ND PLUG AT 610' WITH 50 SX CMT. NO RETURNS. SDFW. 6/14/13: TAG FLUID LEVEL @ 650'. TAG TOC IN 8 5/8" AT 891'. 3RD PLUG AT 650' WITH 60 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5970	5980		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

KCC WICHITA

JUN 20 2013

RECEIVED

District: 01

RECEIVED

JUN 17 2013

KCC DODGE CITY

Signed

(TECHNICIAN)