

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20349-00-00  
Spot: SENWNWNW Sec/Twnshp/Rge: 14-26S-2E  
4715 feet from S Section Line, 4895 feet from E Section Line  
Lease Name: HAMANT Well #: 2-B  
County: SEDGWICK Total Vertical Depth: 3161 feet

Operator License No.: 34381  
Op Name: URBAN OIL AND GAS GROUP LLC  
Address: 1000 E 14TH ST SUITE 300  
PLANO, TX 75074

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3161		360 SX
SURF	8.625	228		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2012 12:00 AM  
Plug Co. License No.: 34231 Plug Co. Name: M & S WELL SERVICE, LLC  
Proposal Rcvd. from: DAVID FRANK Company: URBAN OIL & GAS GROUP LLC Phone: (870) 904-0194

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/13/2012 11:30 AM KCC Agent: DAN FOX

Actual Plugging Report:

Perfs:

PREVIOUS OPERATOR POSSIBLY DROPPED TUBING AND RODS IN HOLE, TAGGED JUNK @ 554' URBAN ATTEMPTED TO FISH TUBING BACK IN MAY OF 2011 BUT ONLY RETRIEVED 8' OF RODS. ON 11/12/2012 A CIBP WAS SET @ 550', DUMPED 2 SX OF CEMENT FOR CAP. PERFORATED 5.50" PRODUCTION CASING @ 280'-281' CIRCULATED CEMENT TO SURFACE WITH 90 SX OF 60/40 POS. MIX W/4% GEL, 1% CC. CONSOLIDATED TICKET #35345, JOB COMPLETE.

KCC WICHITA  
MAY 29 2013  
RECEIVED

Remarks: WELL PLUGGED DUE TO T/A NOV LETTER SENT IN SEPT OF 2012

Plugged through: CSG

District: 02

Signed

  
6/04/13 (TECHNICIAN)