

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22393-00-00  
Spot: W2SESWNW Sec/Twnshp/Rge: 22-32S-14W  
2970 feet from S Section Line, 4440 feet from E Section Line  
Lease Name: JUDY HOAGLAND Well #: 1  
County: BARBER Total Vertical Depth: 4732 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	10.75	293		WITH 205 SX CMT
PROD	4.5	4730	0	WITH 185 SX CMT
SURF	8.625	1010		WITH 100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2013 9:00 AM  
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.  
Proposal Rcvd. from: TRACY BLACK Company: VESS OIL Phone: (316) 215-1873

Proposed Plugging Method: PUMP 10 SX GEL, 200# HULLS & 60 SX CMT. PERFORATE @1030' & CIRCULATE CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE  
Date/Time Plugging Completed: 05/15/2013 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 10 SX GEL, 200# HULLS, & 60 SX CMT VIA TBG. LET CMT SET. TAG TOP WITH WIRELINE @ 2880'. PERFORATE @ 1030'. CIRCULATE CMT TO SURFACE WITH 330 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4628	4642		
4578	4588		
4087	4089		
4078	4080		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

KCC WICHITA

MAY 22 2013

RECEIVED

District: 01

Signed Michael Maier  
6/24/13 (TECHNICIAN)

RECEIVED

MAY 16 2013

KCC DODGE CITY

DN7