

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22578-00-00
Spot: NESWNE Sec/Twnshp/Rge: 8-20S-12W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SCHARTZ Well #: 8-3
County: BARTON Total Vertical Depth: 3595 feet

Operator License No.: 4707
Op Name: BOXBERGER, CARL OIL, INC.
Address: 822 MAIN ST. PO BOX 1604
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3588 | | 150 SX |
| SURF | 8.625 | 310 | | 300 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2013 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: KEITH LUMPKINS Company: BOXBERGER, CARL Phone: (620) 793-6032

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2013 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500', 700' and 305'.
Ran tubing to 3400' and pumped 14 sx gel followed with 50 sx cement w/100 # hulls.
Pulled tubing to 1500' and pumped 80 sx cement w/100 # hulls.
Pulled tubing to 700'. Circulated cement out casing with 125 sx cement and 150 # hulls.
Circulated cement out surface with 50 sx cement. Pulled tubing and topped off with 15 sx cement.

GPS: 38.32895 -098.66957

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3439 | 3442 | | |
| 3428 | 3432 | | |

KCC WICHITA

JUN 05 2013

RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG T6

District: 04

Signed Bruce Rodie
6/21/13 (TECHNICIAN)

CM

MAY 23 2013