

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-21177-00-00  
Spot: SENWNESW Sec/Twnshp/Rge: 34-13S-32W  
2078 feet from S Section Line, 1667 feet from W Section Line  
Lease Name: E & E Well #: 2-34  
County: LOGAN Total Vertical Depth: 4640 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	227		155 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2013 12:00 AM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Rcvd. from: GARY Company: H2 DRILLING LLC Phone: (620) 290-5389

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE  
Date/Time Plugging Completed: 05/25/2013 11:00 PM KCC Agent: DAVID WANN

Actual Plugging Report:

1st plug @2420 w/25 sx  
2nd plug @1350 w/100 sx  
3rd plug @280 w/40 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

KCC WICHITA  
JUN 05 2013  
RECEIVED

District: 04

Signed  (TECHNICIAN)

CM

MAY 29 2013