

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02770-00-01
Spot: SENWSESE Sec/Twnshp/Rge: 33-8S-24W
668 feet from S Section Line, 764 feet from E Section Line
Lease Name: HOLLEY LKC UNIT Well #: 208W
County: GRAHAM Total Vertical Depth: 4021 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PKR | | 3778 | | |
| PROD | 5.5 | 4021 | | 125 SX |
| SURF | 8.625 | 186 | | 150 SX |
| T1 | 2.375 | 3778 | | |

Well Type: EOR UIC Docket No: E09991.3 Date/Time to Plug: 06/03/2013 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: EXPRESS WELL SERVICE & SUPPL Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls and 12 sx gel.
Perforations at 3835' to 3959'.
Shot perforations at 2165' and 1350'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/03/2013 6:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3761' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 2250' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1500' and pumped 150 sx cement w/200 # hulls. Good circulation of cement.
Tied on to backside and squeezed with 40 sx cement. Shut in pressure 400 psi.
Topped off casing with 30 sx cement. Hole standing full.

GPS: 39.30763 -099.99812

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3955 | 3999 | | |
| 3835 | 3959 | | |

KCC WICHITA

JUN 12 2013

RECEIVED

Remarks: SWIFT CEMENT TICKET # 24327

Plugged through: TBG

District: 04

Signed

Marvin Mills
6/19/13 (TECHNICIAN)
cc to WCC 6/13/13

CM

Form CP-2/3

JUN 07 2013