

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20925-00-00
Spot: SWNENW Sec/Twnshp/Rge: 3-17S-12W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: LANG B Well #: 1
County: BARTON Total Vertical Depth: 3331 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD. PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3330		115 SX
SURF	8.625	253		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2013 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 272-1023

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement and 10 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/20/2013 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3000' and pumped 10 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 1400' and pumped 70 sx cement w/100 # hulls.
Pulled tubing to 750' and pumped 50 sx cement w/100 # hulls.
Pulled tubing to 250'. Circulated cement to surface with 115 sx cement.
Circulated cement to surface on surface pipe with 30 sx cement.
Pulled tubing. Topped off with 5 sx

GPS: 38.60554 -098.64160

Perfs:

Top	Bot	Thru	Comments
3330	3331		

Remarks: ALLIED CEMENT CO.

Plugged through: ESG T&G

KCC WICHITA

JUN 05 2013

RECEIVED

District: 04

Signed Bruce Rodie
4/19/13 (TECHNICIAN)

CM

MAY 23 2013