

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23528-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 33-9S-21W
335 feet from S Section Line, 2300 feet from E Section Line
Lease Name: MILFRED Well #: 1-33
County: GRAHAM Total Vertical Depth: 3945 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		
PROD	5.5	3941		175 SX
SURF	8.625	211		150 SX
T1	2.375	3913		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/29/2013 2:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 15 sx gel spacer and 300 # hulls.
Port Collar at 1754'
Perforated 3631' - 3746'
PBTD:3850'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/29/2013 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx 60/40 pozmix 4% gel cement, 15 sx gel spacer followed by 190 sx 60/40 pozmix 4% gel cement. Maximum pressure 500 psi. Shut in pressure 100 psi.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx 60/40 pozmix 4% gel cement. Shut in pressure 500 psi.

GPS: 39.22067N -099.66933W

Perfs:

Top	Bot	Thru	Comments
3885	3889		
3631	3746		

Remarks: SWIFT TICKET # 24616

Plugged through: CSG

KCC WICHITA

JUN 06 2013

RECEIVED

District: 04

Signed Pat Bedore
6/12/13 (TECHNICIAN)

CM

JUN 03 2013