

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21302-00-00
Spot: NWSENE Sec/Twnshp/Rge: 11-29S-10W
4580 feet from S Section Line, 652 feet from E Section Line
Lease Name: ALBERS B Well #: 1
County: KINGMAN Total Vertical Depth: 2700 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2690	1750	175 SX
SURF	8.625	344		275 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/22/2013 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: (316) 215-1873

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 05/23/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2445' - CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1750' PULLED CASING TO 1500', PUMPED 10 SX GEL THEN SPOTTED 35 SX CEMENT. PULLED CASING TO 1000' SPOTTED 35 SX CEMENT. PULLED CASING TO 416' CIRCULATED TO SURFACE WITH 175 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
2543	2548		

KCC WICHITA
JUN 17 2013
RECEIVED

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40/4% POS MIX, TICKET #38579

Plugged through: CSG

District: 02

Signed BJ Hope
6/15/13 (TECHNICIAN)