

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21368-00-00  
Spot: NWSWNENW Sec/Twnshp/Rge: 14-29S-10W  
4607 feet from S Section Line, 3930 feet from E Section Line  
Lease Name: ALBERS F Well #: 1  
County: KINGMAN Total Vertical Depth: 2701 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2699	1620	150 SX
SURF	8	306		275 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/22/2013 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: \_\_\_\_\_ Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/22/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2440' - CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1620' PULLED CASING TO 1500', PUMPED 10 SX GEL THEN SPOTTED 35 SX CEMENT, PULLED CASING TO 1000' SPOTTED 35 SX CEMENT. PULLED CASING TO 374' CIRCULATED TO SURFACE WITH 150 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
2502	2512		

KCC WICHITA  
JUN 17 2013  
RECEIVED

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #38578

Plugged through: CSG

District: 02

Signed BJ Hope  
6/26/13 (TECHNICIAN)