

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20441-00-00
Spot: E2W2NWNE Sec/Twnshp/Rge: 19-25S-4W
4620 feet from S Section Line, 2002 feet from E Section Line
Lease Name: VALDOIS Well #: 2
County: RENO Total Vertical Depth: 4015 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2690	2610	
PROD	5.5	4012		100 SX
SURF	8.5	250		100 SX
SURF	8.625	260		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/28/2013 12:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: (316) 215-1873

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE
Date/Time Plugging Completed: 05/29/2013 4:00 PM

Witness Type: PARTIAL
KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

THERE IS A CIBP SET AT 3240', TOP OF PERFS AT 3198'. 5/29/13 SANDED BACK TO 3140' - CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2610' PULLED CASING TO 736', SPOTTED 35 SX CEMENT. PULLED CASING TO 326' CIRCULATED TO SURFACE WITH 200 SX CEMENT. 6/3/13 SURFACE PLUG FELL BACK 81', TOOK 8 SX OF CEMENT TO FILL, WELDED PLATE ON SURFACE CASING.

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #38585

Plugged through: CSG

KCC WICHITA

JUN 17 2013

RECEIVED

District: 02

Signed BJ Hope
6/26/13 (TECHNICIAN)