

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21590-00-00  
Spot: NWSESWNE Sec/Twnshp/Rge: 27-21S-16W  
2976 feet from S Section Line, 1661 feet from E Section Line  
Lease Name: BELL Well #: 1-27  
County: PAWNEE Total Vertical Depth: 4015 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 3840       |             |                 |
| CIBP   |       | 3876       |             |                 |
| PC     |       | 2140       |             | WITH 230 SX CMT |
| PROD   | 5.5   | 4009       | 0           | WITH 200 SX CMT |
| SURF   | 8.625 | 1034       |             | WITH 370 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2013 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L LOEB LLC Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP @ 3440' & 2 SX CMT. RUN TBG TO 1060' & CIRCULATE CMT TO SURFACE. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/06/2013 12:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3440' WITH 2 SX CMT ON TOP WITH DUMP BAILER. RAN TBG TO 1064' & PUMPED 100 SX CMT CIRCULATING CMT TO SURFACE UP THE 5 1/2" CASING. PULLED TBG OUT & TOPPED OFF 5 1/2" WITH 12 1/2 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG INSTANTLY WITH CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3878 | 3882 |      | ARBUCKLE |

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA  
JUN 10 2013  
RECEIVED

District: 01

RECEIVED

JUN -7 2013

KCC DODGE CITY

Signed

Richard W. Lacey  
6/25/13 (TECHNICIAN)

*ROW*