

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25570-00-00
Spot: N2NWSWNE Sec/Twnshp/Rge: 35-18S-22W
1600 feet from N Section Line, 2310 feet from E Section Line
Lease Name: WITTHUHN HEIRS Well #: 3-35
County: NESS Total Vertical Depth: 4269 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	224		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/24/2013 8:45 PM
Plug Co. License No.: 33323 Plug Co. Name: PETROMARK DRILLING, LLC
Proposal Rcvd. from: KENNY ROACH Company: PETROMARK DRILLING, LLC Phone: (316) 734-8977

Proposed Plugging Method: 1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 05/24/2013 10:45 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA
JUN 10 2013
RECEIVED

District: 01

Signed _____

RECEIVED

JUN - 4 2013

KCC DODGE CITY

(TECHNICIAN)