

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22005-00-01
Spot: NENENE Sec/Twnshp/Rge: 6-34S-38W
5027 feet from S Section Line, 302 feet from E Section Line
Lease Name: BANE TRUST A Well #: 1-6
County: STEVENS Total Vertical Depth: 6400 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6150		WITH 2 SX CMT
DVT		3087		WITH 375 SX CMT
PROD 4.5		6394	1408	WITH 575 SX CMT
SURF 8.625		1472		WITH 900 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/30/2013 12:00 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: SET CIBP @ 6150' WITH 2 SX CMT. PLUG AT TOP OF STUB WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/30/2013 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 6150' WITH 2 SX CMT. 1ST PLUG AT 1408' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6180	6222		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
JUN - 7 2013
KCC DODGE CITY

Signed _____

[Signature]
6/19/13 (TECHNICIAN)

KCC WICHITA
JUN 10 2013
RECEIVED

ADNY