

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22467-00-00
Spot: E2SE Sec/Twnshp/Rge: 21-33S-14W
1332 feet from S Section Line, 648 feet from E Section Line
Lease Name: HARBAUGH A Well #: 2-21
County: BARBER Total Vertical Depth: 5150 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4600		WITH 2 SX CMT
CIBP		4930		WITH 2 SX CMT
PROD	5.5	5150	2532	WITH 275 SX CMT
SURF	8.625	1100		WITH 525 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/21/2013 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP'S AT 4930' & 4600' WITH 2 SX CMT ON TOP OF EACH CIBP. PLUG AT 1130' WITH 20 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2013 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP'S @ 4930' & 4600'. PUT 2 SX CMT ON TOP OF EACH CIBP. 1ST PLUG AT 1132' WITH 200# HULLS IN WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 314' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4986	4992		
4953	4957		
4642	4680		

KCC WICHITA

JUN 07 2013

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

JUN - 3 2013

KCC DODGE CITY

Signed

Stephen J Pfeifer
(TECHNICIAN)
6/20/13