

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-19127-00-01
Spot: NWSWNENE Sec/Twnshp/Rge: 33-21S-14W
4316 feet from S Section Line, 985 feet from E Section Line
Lease Name: NORB KRAMPE Well #: 2
County: STAFFORD Total Vertical Depth: 3870 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1074		
PLG	5.5	3841		
PROD	5.5	3868	0	160 SX
SURF	8.625	284		350 SX

Well Type: WSW UIC Docket No: E17848.1 Date/Time to Plug: 06/14/2013 2:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DANIEL Company: CITATION OIL & GAS Phone: (405) 605-9177

Proposed Plugging Method: RUN TBG TO MAXIMUM DEPTH. BOTTOM PLUG: IF ABLE TO GET TO BELOW 3060', PUMP 50 SX CMT. TOP PLUG: PULL TBG TO 1000' & CIRCULATE CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2013 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

AFTER MANY DAYS OF WORK COMPANY WAS ABLE TO FISH OUT TBG & PACKER. HAD HARD TIME GETTING TBG BACK PAST 400'. AFTER FEW MORE DAYS OF WORK WAS ABLE TO GET TO 1070' & DETERMINED THAT DOWN HOLE EQUIPMENT WAS OUTSIDE THE CASING. DECISION WAS MADE TO DO AN EMERGENCY PLUG JOB SINCE IT WAS UNLIKELY THAT COMPANY COULD BACK DOWN THIS DEEP AFTER THE WEEKEND. RAN TBG BACK TO 1040' PUMPED 440 SX CMT CIRCULATING CMT TO SURFACE UP 5 1/2" CASING. GOOD RETURNS DURING PUMP JOB. PULLED TBG OUT OF HOLE & TOPPED OFF 5 1/2" WITH 30 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 1400 PSIG WITH 2 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3550	3635		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
JUN 17 2013
KCC DODGE CITY

Signed

Richard W. Lacey
6/21/13

(TECHNICIAN)

KCC WICHITA

JUN 20 2013

RECEIVED