

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-23697-00-00
Spot: SWNW Sec/Twnshp/Rge: 32-22S-19E
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: CONLEY Well #: BC 6.5 W
County: ANDERSON Total Vertical Depth: 870 feet

Operator License No.: 30948
Op Name: CONLEY, HARRY
Address: 19334 SW 500 RD
COLONY, KS 66015

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	847		
PROD	2.875	865		55 SX
SURF	8	20		7 SX

Well Type: EOR UIC Docket No: E26592.2 Date/Time to Plug: 05/28/2013 1:00 PM
Plug Co. License No.: 30948 Plug Co. Name: CONLEY, HARRY
Proposal Rcvd. from: HARRY CONLEY Company: Phone: (620) 852-3038

Proposed Plugging Method: circulate cement through one inch bottom to top.

Plugging Proposal Received By: LARRY MARCHANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/28/2013 4:00 PM KCC Agent: LARRY MARCHANT

Actual Plugging Report:

Squeeze from surface to perforations at 200 PSI with portland and cotton seed hulls. Cement and hulls block perms. Pressured up to 600 PSI and shut in. used 27 sacks portland type 1 and 25 lbs. hulls.

Perfs:

Top	Bot	Thru	Comments
810	818		
RECEIVED JUN 04 2013 KCC Chanute Dist. #3 LM			

KCC WICHITA

Remarks: COULD NOT GET DOWN WELL WITH 1".

JUN 06 2013

Plugged through: CSG

RECEIVED

District: 03

Signed

Larry Marchant
6/20/13 (TECHNICIAN)

cc to WCC 6/17/13