

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02982-00-01
Spot: SENENW Sec/Twnshp/Rge: 5-8S-17W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ECKERT 'A' Well #: 1
County: ROOKS Total Vertical Depth: 550 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY STE 3700
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	8.625	131		60 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 03/20/2013 11:30 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: RALPH BRUNGARDT Company: SCHIPPERS OILFIELD SERVICES, L Phone: (785) 735-4645

Proposed Plugging Method:	Ordered 275 sx 60/40 pozmix 4% gel cement. Got to 1500' while drilling out hole went out at casing. Spotted 100 sx cement at 1500'. Tried to drill back out but went out and well started flowing back at 550'. Shut in. GPS: 39.39109 -099.24160
---------------------------------	---

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2013 11:30 AM KCC Agent: TOM CULLEY

Actual Plugging Report:

Perfs:

Ran tubing to 400' and stacked out. Tried to circulate hole clean to 550'. Could not get tubing down. Circulated from 400' w/275 sx cement. POOH. Pressured 8 5/8" casing to 250 psi.

Remarks: SOS TICKET # 679

Plugged through: TBG

KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed _____

Tom Culley
6/20/13 (TECHNICIAN)

CM

MAR 27 2013
~~MAR 20 2013~~