

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21626-00-00
Spot: N2NWSWSW Sec/Twnshp/Rge: 17-16S-13W
1250 feet from S Section Line, 330 feet from W Section Line
Lease Name: STOSKOPF A Well #: 12
County: BARTON Total Vertical Depth: 3387 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3385		150 SX
SURF	8.625	356		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2013 11:00 AM
Plug Co. License No.: 5121 Plug Co. Name: MOBILE DRILLING COMPANY, INC.
Proposal Rcvd. from: WILL DARRAH Company: DARRAH, JOHN Phone: (316) 219-3390

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2013 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 750' and 240'.
Ran tubing to 3202' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 1570' and pumped 85 sx cement w/150 # hulls.
Pulled tubing to 800'. Circulated cement to surface with 90 sx cement w/150 # hulls.
Circulated cement to surface on surface pipe with 5 sx cement.
Pulled tubing. Topped off with 5 sx cement.

GPS: 38.65554 -098.79216

Perfs:

Top	Bot	Thru	Comments
3385	3387		
844	844		

KCC WICHITA

JUN 05 2013

RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG 136

District: 04

Signed Bruce Rodie
6/20/13 (TECHNICIAN)

CM

MAY 23 2013