

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-00425-00-01
Spot: N2S2NWSE Sec/Twnshp/Rge: 9-31S-15W
1909 feet from S Section Line, 1957 feet from E Section Line
Lease Name: NATIONAL GYPSUM A Well #: 2
County: BARBER Total Vertical Depth: 4922 feet

Operator License No.: 33450
Op Name: TERRA FIRMA EXPLORATION, INC.
Address: 12601 JAYSON LN
WICHITA, KS 67235

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3281		
MSCC		3410		175 SX CMT.
PROD	5.5	4920		325 SX CMT.
SURF	10.75	757		500 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/07/2013 4:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK TO 3165' & 5 SX CMT. PLUG AT 780' WITH 20 SX GEL & 75 SX CMT. PLUG AT 360' WITH 75 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 05/07/2013 5:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 3140' & PUT 2 SX CMT ON TOP OF CIBP THOROUGH DUMP BAILER. 1ST PLUG AT 787' WITH 20 SX GEL & 75 SX CMT. 2ND PLUG AT 360' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 45 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4655	4660		
4448	4454		
3287	3291		
3272	3278		
3258	3261		
3236	3244		
3214	3224		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 20 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

MAY 14 2013

KCC DODGE CITY

Signed

(TECHNICIAN)