

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21297-00-00
Spot: E2NWNWNW Sec/Twnshp/Rge: 14-11S-31W
4950 feet from S Section Line, 4840 feet from E Section Line
Lease Name: KEARNS Well #: 1
County: GOVE Total Vertical Depth: 4622 feet

Operator License No.: 4656
Op Name: DAVIS PETROLEUM, INC.
Address: 7 SW 26 AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4619		600 SX
SURF	8.625	351		195 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/10/2013 10:00 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: MIKE KASSELMAN Company: SCHIPPERS OILFIELD SERVICES, L Phone: (620) 793-3051

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 8 sx gel and 400 # hulls.
DV Tool set at 2519' w/350 sx cement.
Perforations: 4503' - 4506', 4493' - 4497', 4429' - 4431', 4261' - 4264', 4233' - 4236', 4296' - 4299'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/10/2013 4:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 50 sx cement w/200 # hulls.
Followed by 5 sx gel, followed by 350 sx cement w/200 # hulls. Kept falling. Will go back and try to top off.
Topped off casing with 50 sx cement. Hole standing full.
Tied on to back side and pumped 30 sx cement. Hole standing full.
GPS: 39.10359 -100.73706

Perfs:

Top	Bot	Thru	Comments
4503	4506		
4493	4497		
4429	4431		
4296	4299		
4261	4264		
4233	4236		

Remarks: SOS CEMENT TICKET # 1039

Plugged through: CSG

KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed Marvin Mills
6/26/13 (TECHNICIAN)

CM

JUN 12 2013