

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23067-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 10-21S-11W
440 feet from N Section Line, 1980 feet from E Section Line
Lease Name: FAIR A Well #: 1-10
County: STAFFORD Total Vertical Depth: 2660 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2527		
PROD	4.5	2556	0	WITH 50 SX CMT
SURF	8.625	228		WITH 240 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/17/2013 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 2230' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 05/17/2013 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 2230' & 4 SX CMT. PERFORATED @ 600'. RAN TBG TO 600' PUMPED 50 SX CMT. PULLED TBG TO 260' PUMPED 50 SX CMT. CMT CIRCULATED UP 8 5/8" X 4 1/2" ANNULUS. PULLED TBG TO 40' PUMPED 20 SX CMT. PULLED TBG OUT & TOPPED OFF HOLE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2376	2378		
2363	2364		
2286	2288		

KCC WICHITA
JUN 20 2013
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey
6/25/13

(TECHNICIAN)

RECEIVED

JUN 17 2013

KCC DODGE CITY