

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20947-00-02
Spot: SWSE Sec/Twnshp/Rge: 36-34S-36W
670 feet from S Section Line, 1976 feet from E Section Line
Lease Name: ROEHR SWD Well #: 2 I
County: STEVENS Total Vertical Depth: 6800 feet

Operator License No.: 34745
Op Name: GLOBE ENERGY SERVICES LLC
Address: 1015 N. COLLEGE AVE. PO BOX 255
SNYDER, TX 79550

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	16	30		3 YRD
PROD	4.5	6800	0	WITH 150 SX CMT
SURF	8.625	1691		WITH 750 SX CMT

Well Type: SWD UIC Docket No: D27649.0 Date/Time to Plug: 05/09/2013 8:00 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: JAMES BENTLEY Company: NORTEX Phone:

Proposed
Plugging
Method:

WILL PLUG BASED ON APPROVAL PLUGGING PROCEDURE ESTABLISHED BY THE KCC.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2013 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

RAN TENSION PACKER ON 1" TBG TO 651' INSIDE 2 3/8" TBG. PUMPED 50 SX CLASS A CMT & DISPLACE WITH 10 BBL WATER. AFTER 4 HOURS, TAG TOC INSIDE THE 2 3/8" TBG @ 4315'. TAG W/WIRELINE @ 4136'. 1/31/13: 2 3/8" TBG CLEANED OUT WITH COIL TBG TO 5801'. 5/2/13: RAN TEMPERATURE SURVEY INDICATING A HOLE @ 5340'. RAN R.A. TRACER SURVEY. APPROXIMATELY 20% OF INJECTED FLUID GOING DOWN THE 2 3/8" TBG & 80% GOING DOWN THE 2 3/8" X 4 1/2" ANNULUS. 5/10/13: RAN TENSION PACKER ON 1 1/2" TBG INSIDE THE 2 3/8" TBG & PUMPED THE ABOVE BOTTOM PLUG. 5/13/13: FISHED OUT 2 3/8" TBG & 4 1/2" CASING TO 378'. 5/14/13: ATTEMPT TO SHOOT OFF TBG & CASING SIMULTANEOUSLY @ 1494'. COULD NOT PULL EITHER. ATTEMPT TO RUN SECOND SPLIT SHOT. COULD NOT GET PAST 455' IN THE 2 3/8". 5/15/13: ATTEMPT TO RUN 2 1/16" TBG DOWN 2 3/8" X 4 1/2" ANNULUS TO 1700'. COULD NOT GET PAST 911'. PULLED UP TO 881' & PUMPED 150 SX CMT. NO CIRCULATION. 5/16/13: TAG TOC IN THE 8 5/8" CASING @ 303'. CIRCULATE CMT TO SURFACE WITH 200 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
6535	6540		

Remarks: USED CLASS A COMMON CEMENT BY PHIL DOLLAR.

Plugged through: TBG

KCC WICHITA

JUN 17 2013

RECEIVED

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

JUN 12 2013

KCC DODGE CITY

AWT