

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1964
2-14-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Socony Mobil Oil Co., Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name Wm. L. Carr Well No. # 1

Location SW NW NW Sec. 31 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4460

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 10:00AM Day 13th Month Feb. Year 1964

The Above well was plugged as follows:

250' of 9 5/8" surface pipe, cemented with 255 sacks. 4459' of 5 1/2" long
string, cemented with 200 sacks. Plug back to 4422'. Top perforation
4383'. Bottom of hole was sanded to 4375', and cemented with 5 sacks.
Fluid in hole was at 278'. Plug was set at 278', with 10' rock bridge,
and 35 sacks cement on plug, bringing the cement to 210' in the surface pipe.
Hole was filled with mud to 40', with 10' rock bridge, and cemented with
12 sacks to base cellar.

3190' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/14/64
INV. NO. 8646-W