

15-077-00957-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1966
7-13-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Bulldog Pipe & Supply

Complete Address: P. O. Box 1153, Tulsa, Oklahoma

Lease Name Harry Burgess Well No. # 2

Location NW NW NE Sec. 21 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4528'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 1:45 PM Day 9th Month July Year 1966

The Above well was plugged as follows:

.181' of 8 5/8" surface pipe, cemented with 150 sacks. 4527' of 5 1/2" long
string, cemented with 150 sacks. Top perforation 4399'. Bottom of the
hole was sanded to 4375', and cemented with 5 sacks, through the dump
bailer. 3778' of 5 1/2" long string was recovered from the hole. Hole was
filled with mud to 200', rock bridge from 200' to 190', and cemented
with 25 sacks, bringing the top of the cement to 120' in the surface
pipe. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/13/66

INV. NO. 3558-W