

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21532-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 15-28S-20W
1972 feet from S Section Line, 1930 feet from W Section Line
Lease Name: CLAYTON Well #: 1
County: KIOWA Total Vertical Depth: 5150 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4963		
PROD	4.5	5144	1315	WITH 150 SX CMT
SURF	10.75	310		WITH 275 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/11/2013 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: CARL W. DURR Company: WOOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: SAND TO 2876' WITH 2 SX CMT. PLUG AT 1290' WITH 12 SX GEL & 75 SX CMT. PLUG AT 330' WITH 75 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 06/11/2013 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SANDED TO 4869' WITH 2 SX CMT. 1ST PLUG AT 1290' WITH 12 SX GEL & 75 SX CMT. 2ND PLUG AT 330' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4966	4970		CIBP@4963
4926	4932		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

[Handwritten Signature]
7/10/13
(TECHNICIAN)

RECEIVED
JUN 12 2013
KCC DODGE CITY

KCC WICHITA

JUN 20 2013 Form CP-2/3

RECEIVED

[Handwritten Initials]