

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-05282-00-00
Spot: NENE Sec/Twnshp/Rge: 9-1S-34W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: TEXACO CAHOJ Well #: 9
County: RAWLINS Total Vertical Depth: 4286 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4141		
PROD	5.5	4284		250 SX
SURF	8.625	371		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/31/2013 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: SWIFT SERVICES Phone: (800) 962-1206

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
CIBP at 4141'
Production perforations: 3972' - 3975', 3980' - 3988', 4114' - 4116' and 4131' - 4134'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/31/2013 12:00 PM KCC Agent: TOM CULLEY

Actual Plugging Report:

Ran tubing to 3893' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2907' and pumped 100 sx cement. Pulled tubing to 1897' and pumped 100 sx cement w/200 hulls. Pulled tubing to 884' and pumped 100 sx cement. PTOH. 25 sx cement down back side. Shut in pressure 300 psi. Topped off casing with 25 sx cement.

GPS: 39.98565 -101.13276

Perfs:

Top	Bot	Thru	Comments
4198	4205		
4162	4164		
4131	4134		
4114	4116		
3980	3988		
3972	3975		

Remarks: SWIFT SERVICES TICKET # 24281

Plugged through: TBG

KCC WICHITA
JUN 19 2013
RECEIVED

District: 04

Signed _____

[Signature]
TECHNICIAN) *cm*

JUN 10 2013