

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20428-00-00
Spot: NWSENE Sec/Twnshp/Rge: 15-26S-2E
4620 feet from S Section Line, 760 feet from E Section Line
Lease Name: LYGRISSE Well #: B 3
County: SEDGWICK Total Vertical Depth: 3168 feet

Operator License No.: 34381
Op Name: URBAN OIL AND GAS GROUP LLC
Address: 1000 E 14TH ST SUITE 300
PLANO, TX 75074

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3158		0 SX
SURF	8.625	216		150 SX
TI	2.875	3164		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2013 8:00 AM
Plug Co. License No.: 34231 Plug Co. Name: M & S WELL SERVICE, LLC
Proposal Rcvd. from: KRISTIN GRAGG Company: URBAN OIL & GAS GROUP, LLC Phone: (972) 543-8824

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2013 8:30 AM KCC Agent: DAN FOX

Actual Plugging Report:

ON 3/23/2013 A CIBP WAS SET @ 3130'. CAPPED WITH (2) 100 LB SXS OF CEMENT. TAGGED TOP OF CAP @ 3107'. PERFORATED 5.500' PROD. CASING @ 266' W/4 SHOTS CIRCULATED CEMENT TO SURFACE WITH 72 SX OF 60/40 POS MIX WITH 4% GEL, 2% CC. CONSOLIDATED TICKET #38460, JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
3158	3164		

KCC WICHITA
JUN 17 2013

Remarks: WELL PLUGGED DUE TO COMMISSION ORDER DOCKET #13-CONS-272-CPEN RECEIVED
Plugged through: TBG

District: 02 Signed: [Signature]
7/07/13 (TECHNICIAN)