

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-01360-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 9-30S-2W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LOVE Well #: 6
County: SUMNER Total Vertical Depth: 3248 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3164		150 SX
SURF	12.5	40		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2013 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TRACY BLACK Company: _____ Phone: (316) 215-1873

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 02/08/2013 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

RIGGED UP AND TAGGED BOTTOM @ 3200'. SAND OFF OPEN HOLE @ 3100, DUMPED 10 SX CEMENT CAP. WAITED ON WELDER TO WELD 2" COLLAR ON SURFACE PIPE DUE TO WRONG THREAD. PERF CASING @ 450', RUN TUBING AND SPOT 50 SX CEMENT, PRESSURE IT IN. PERF @ 250', PUMPED 100 SX 60/40 POZMIX AND CIRCULATE UP BACKSIDE, TOP OFF WITH 5 SX.

Perfs:


Top	Bot	Thru	Comments
3164	3212		

Remarks: COPELAND ACID & CEMENT. TICKET #C38239

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

KCC WICHITA

JUN 24 2013

Form CP-2/3

RECEIVED

✓ 7/07/13

✓ SK