

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21191-00-00
Spot: SENENWSW Sec/Twnshp/Rge: 32-22S-30W
2286 feet from S Section Line, 4287 feet from E Section Line
Lease Name: TARPLEY Well #: 1-32
County: FINNEY Total Vertical Depth: 4860 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		2094		WITH 453 SX CMT
PROD	4.5	4857	0	WITH 150 SX CMT
SURF	8.625	351		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2013 1:30 PM
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: TBG TO 4580' WITH 35 SX CMT, 10 SX GEL & 100# HULLS. PLUG AT 2040' WITH 30 SX CMT. PLUG AT 1300' WITH 30 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 06/14/2013 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BOTTOM PLUG AT 4595' WITH 10 SX GEL, 35 SX CMT & 100# HULLS. 1ST PLUG AT 2055' WITH 30 SX CMT. 2ND PLUG AT 1297' WITH 30 SX CMT. 3RD PLUG AT 601' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 25 SX CMT. CHECK BACKSIDE WITH 25 SX CMT. HELD AT 500#.

Perfs:

Top	Bot	Thru	Comments
4584	4591		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

KCC WICHITA

JUN 24 2013

RECEIVED

RECEIVED

JUN 17 2013

KCC DODGE CITY

Form CP-2/3

AMV