

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21061-00-00
Spot: NENWNE Sec/Twnshp/Rge: 25-15S-12W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: STAUDINGER Well #: 1
County: RUSSELL Total Vertical Depth: 3365 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3364		100 SX
SURF	8.625	218		230 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2013 8:00 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: DAN WEINHOLD Company: GLM COMPANY Phone: (785) 483-1307

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 500 # hulls and 10 sx gel.
Perforations at 1500', 775', 475' and 220'.
Shot off 2.875" at 2856' leaving 500' in well

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/18/2013 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2830' and pumped 5 sx gel followed by 75 sx cement w/200 # hulls.
Pulled tubing to 1550' and pumped 185 sx cement w/200 # hulls.
Cement circulated out the back side. Shut in. Pumped 35 sx cement and circulated cement out the braden head. Shut in. POOH. Hooked to casing and pumped 10 sx cement at 250 psi. Shut in.

GPS: 38.72514 -098.60263

Remarks: QUALITY CEMENTING TICKET # 6391

Plugged through: TBG

KCC WICHITA

JUN 26 2013

RECEIVED

District: 04

Signed Ray Dinkel
7/04/13 (TECHNICIAN) CM

JUN 20 2013