

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02763-00-00
Spot: S2SWSW Sec/Twnshp/Rge: 33-8S-24W
330 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HOLLEY Well #: 201
County: GRAHAM Total Vertical Depth: 4035 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD. PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4019		
PROD	5.5	4035		100 SX
SURF	8.625	220		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2013 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: EXPRESS WELL SERVICE & SUPPL Phone: (620) 275-2963

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 7 sx gel and 500 # hulls.
Perforations at 3957' - 3980'.
Shot perforations at 2150' and 1350'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2013 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3882' and pumped 7 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 2250' and pumped 75 sx cement w/200 # hulls.
Pulled tubing to 1150' and pumped 100 sx cement w/200 # hulls. Good circulation of cement.
Tied on to back side and squeezed with 50 sx cement. Shut in pressure 100 psi.
Topped off casing with 15 sx cement. Hole standing full.

GPS: 39.30672 -100.01191

Perfs:

Top	Bot	Thru	Comments
3957	3980		

Remarks: SWIFT CEMENT TICKET # 24328

Plugged through: TBG


KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed


6/28/13 (TECHNICIAN)

CM

JUN 19 2013