

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21735-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 6-13S-31W
330 feet from N Section Line, 2310 feet from E Section Line
Lease Name: HULLET Well #: 3-6
County: GOVE Total Vertical Depth: 4715 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2272		
PROD	4.5	4714		550 SX
SURF	8.625	221		170 SX
T1	2.375	4641		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/12/2013 1:30 PM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: LARRY KARLIN Company: H2 PLAINS, LLC Phone: (620) 805-1300

Proposed Perforations: 4542' - 4546', 4546' - 4554', 4562' - 4567', 4614' - 4619'.
Plugging Ordered 350 sx 60/40 pozmix 4% gel cement, 10 sx gel and 400 # hulls.
Method: DV Tool at 2271' w/450 sx cement.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2013 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4500' and pumped 10 sx gel followed by 60 sx cement w/150 # hulls.
Pulled tubing to 2560' and pumped 90 sx cement.
Pulled tubing to 1300' and pumped 90 sx cement. Good circulation of cement.
Topped off casing with 30 sx cement. Hole standing full.
Tied on to back side and squeezed w/10 sx cement. Shut in pressure 100 psi.

GPS: 38.95964 -100.80471

Perfs:

Top	Bot	Thru	Comments
4542	4546		

Remarks: CONSOLIDATED CEMENT TICKET # 39944

Plugged through: TBG

KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed Marvin Mills
6/26/13 (TECHNICIAN)

CM

JUN 14 2013