

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24980-00-00
Spot: N2SESENE Sec/Twnshp/Rge: 5-16S-11W
2020 feet from N Section Line, .330 feet from E Section Line
Lease Name: DAVIDSON Well #: 1
County: BARTON Total Vertical Depth: 3294 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3220		
PROD	5.5	3293	1500	135 SX
SURF	8.625	393		225 SX
T1	2.875	3215		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2013 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL CORP. Phone: (785) 483-2169

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/15/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped with 5 sx cement.
Cut casing at 1500'. Pulled to 1480'. Tied to casing and pumped 125 sx cement w/200 # hulls.
Pulled casing to 750' and pumped 50 sx cement w/100 # hulls.
Pulled casing to 450' and pumped 150 sx cement. Circulated cement to surface.
Pulled casing. Hole stayed full.

GPS: 38.69130 -098.54114

Perfs:

Top	Bot	Thru	Comments
3248	3252		
3122	3126		
3095	3099		
3086	3090		
3052	3056		
3003	3007		
2959	2963		
2935	2940		
2908	3126		

Remarks: ALLIED CEMENTING

Plugged through: CSG

KCC WICHITA

JUN 05 2013

RECEIVED

District: 04

Signed Bruce Rodie
6/24/13 (TECHNICIAN)

CM

MAY 23 2013