

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-20200-00-01  
Spot: SWNW Sec/Twnshp/Rge: 24-32S-8W  
1980 feet from N Section Line, 660 feet from W Section Line  
Lease Name: JAYHAWK 'A' OWWO Well #: 1-24  
County: HARPER Total Vertical Depth: 4515 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4491		
PROD	4.5	4514	3811	200 SX
SURF	8.625	253		200 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2013 12:00 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: SCOTT HAMPEL Company: \_\_\_\_\_ Phone: (316) 636-2737

Proposed Plugging Method: Set Cast Iron Plug at 4400' Set 2 sacks on top of of Cast Iron Plug. Pull pipe. At 300', circulate cement to surface. Use 60/40 Pozmix with 4% Gel.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/21/2013 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP AT 4480' WITH 2 SX CEMENT ON TOP. RAN FREEPOINT. SHOT 4 1/2" CASING OFF AT 3811'. PULLED CASING UP TO 1269' AND SET 35 SX PLUG. PULLED TO 803' AND SET 35 SX PLUG. PULLED TO 337' AND CEMENTED TO SURFACE WITH 95 SXS. TOPPED OFF WITH 20 SXS. ALLIED CEMENTING USED 185 SXS OF 60/40 POZMIX. WITNESSED BY STEVE VANGIESON WITH KCC. RECOVERED 90 JTS OF 4 1/2", 10.5# CASING.

Perfs:


Top	Bot	Thru	Comments
4458	4468		

Remarks:

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

KCC WICHITA

JUN 24 2013

RECEIVED

✓JK