

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15- 101-21783-0000

LEASE NAME Clark

WELL NUMBER 1-15

2,310 Ft. from S Section Line

1,320 Ft. from ^WE Section Line

SEC. 15 TWP. 19 RGE. 29 ~~(E)~~ or (W)

COUNTY Lane

Date Well Completed 11-15-00

Plugging Commenced 11-15-00

Plugging Completed 11-15-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Larson Operating Co.

ADDRESS 562 West Highway 4, Olmitz, KS 67546

PHONE/(316) 653-7368 OPERATORS LICENSE NO. 3842

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-15-00 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	261'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 2,200', spot 50 sax cement on plug thru drill pipe; push bridge plug to 1,330', spot 80 sax cement on plug thru drill pipe; push bridge plug to 750', spot 40 sax cement on plug thru drill pipe; push bridge plug to 280', spot 40' sax cement on plug thru drill pipe; push bridge plug to 40', dump 10 sax cement on plug; dump 15 sax cement down rat hole and 10 sax cement down mouse hole

Name of Plugging Contractor SHIELDS DRILLING CO. License No. RECEIVED

Address PO Box 709, Russell, KS 67665 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Larson Operating Co. NOV 28 2000

STATE OF KANSAS COUNTY OF RUSSELL, ss. NOV 28 2000

Jack P. Beeman, Sec.-Treas (EMPLOYEE of Operator) or Contractor

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 27th day of November 2000

Lucretia Phillips
Notary Public

My Commission Expires: _____

State of Kansas
My Appt. Exp. 5-26-03

Form CP-
Revised 05-8