

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20.280 - 0000

LEASE NAME Paris A

WELL NUMBER 1

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 14 TWP. 19S RGE. 29W (E) or (W)

COUNTY Lane

Date Well Completed 01-17-78

Plugging Commenced 10-23-97

Plugging Completed 10-23-97

10-29-97
TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR JHS Energy, Inc.

ADDRESS 1720 S. Bellaire Street, Suite 1208, Denver, CO. 80222

PHONE# (303) 757-8811 OPERATORS LICENSE NO. 31645

Character of Well Oil

(Oil, Gas, p&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-23-97 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top 4190 Bottom 4395 T.O. 4720

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	260	0
	Production			4 1/2"	4719	665

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Bottom plug sand and cement to 4140'. Allied mixed 80 sacks 60/40 6% gel-1/4# flo seal, @ 1350' mixed 50 sacks @ 650' - mixed 40 sacks @ 290' - 20 sacks @ 40, circulated cement- topped off - stayed. Max psi 500#, Time started 12:20 pm, completed 2:00 pm

Name of Plugging Contractor D. S. & W. Well Servicing, Inc. License No. 6901

Address P. O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JHS Energy, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Joseph E. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Joseph E. Strube

(Address) P. O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 97

Bonnie L. Connell
Notary Public

My Commission Expires: April 8, 2001

USE ONLY ONE SIDE OF EACH FORM

